Feet Survey No. 4048

EXPENDITURE OF FIVE HUNDRED DOLLARS-Continued.

No. 3. A shaft, the westerly end of which bears from corner No. 2 N. 54° 30' E. 402 feet, 4 ft. by 6 ft. by 10 ft deep.

Value $50.00

Other Improvements
None

INSTRUMENT

This survey was made with a C. L. Berger Mining Transit No. 3942. The courses were deflected from a true meridian determined by direct solar observations. The distances were measured with 100 ft. and 500 ft. steel tapes.

REPORT.

The northerly side line of this location was run directly upon the ground and the several corners established by means of off-sets from the side line. The tie line was run by a traverse, run upon the ground and submitted in a separate report herewith.

The ¼ section corner between sections 8 and 17 T. 13 N. R. 26 E., M. D. B. and M. is a granite stone, 6 inches above the ground, 5 inches by 6 inches on the upper face, in the center of which a cross has been chiseled. This is the nearest standing corner of the public survey that can be found and identified.
Survey No. 3989, Copper Ridge No. 3 lode.
Corners 1 and 4 are redwood posts, properly set and scribed with the number of the corner and survey. I find the courses of lines 4-1 and 3-4 to be correct as approved.

Survey No. 3989, Copper Ridge No. 4 Lode.
Corner No. 1 is identical with corner No. 4, Survey No. 3989, Copper Ridge No. 3 lode, a redwood post properly set and scribed with the number of the corner and survey.

Corner No. 2 is not standing, and the course of line 1-2 as herein given was determined by measuring to the center of the mound of stones which marks the position of the corner.

I find the courses of line 1-2 and 4-1 to be correct as approved.

Survey No. 3514- Grubstake lode.

Corners No. 3 and 4 are pine posts properly set and scribed with the number of the corner and survey.
I find line 3-4 to be S. 81° 36' W. 1498.2 feet instead of S. 81° 43' 30" W. 1497.54 feet as approved.

Corner No. 1 is a pine post properly set and scribed with the number of the corner and survey.

I find line connecting Corner No. 1, Grubstake Lode, with the ¼ section corner between sections 8 and 17 T. 13 N., R. 26 E., M. D. B. and M. to be N. 28° 05' 40" W. 5794.6 feet instead of N. 28° 00' W. 5799.4 feet as approved.